

MIRANDA HOUSE

UNIVERSITY OF DELHI

Notice Inviting Quotation

Sealed quotation an invited from the civil working contractors of the College/CPWD/Delhi University.

"Repair and distemper work in Non Teaching Flats D-97 & 89"

Publishing Date	08-08-24 1.00 P.M
Estimated Cost	61000
Completion Time	30 Days
Quotation Submission Date	16-08-24 3.00 P.M

- Bids will be opened as per date/time on mentioned above.
- The above Quotation should reach Miranda House College Office by hand on or before 16.08.24 up to 3.00 p.m.
- The unit rate for any items should be Quotation inclusive of GST.
- For general rules and directive condition of contract, the tender shall refer to "CPWD General condition of contract-2014.

↓
7/8/24

2
07/07/24

MIRANDA HOUSE

UNIVERSITY OF DELHI

QUATATION

Repair and Distempering work in Non Teaching Flats-97,89.

S.NO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer (Note-Rate coated with scaffolding system including in the item)	348	Sqm		
2	12 mm cement plaster of mix : 13.1.1 1:4 (1 cement: 4 fine sand) (Note-Rate coated with scaffolding system including in the item)	45	Sqm		
3	Providing and fixing BRC Jali fixing in RCC surface	10			
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : 13.61.1 Two or more coats on new work	102	Sqm		

5	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	2	Sqm		
6	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse	1	Sqm		
7	Providing Carpenter for wooden work	3	Days		
				Total	

Bde
PRINCIPAL