

MIRANDA HOUSE
UNIVERSITY OF DELHI

Date: 19.02.2022


Notice Inviting Quotation

Sealed quotation an invited from the civil working contractors of the College/ CPWD/ Delhi University.
"Providing & Fixing APP sheet on roof of NCC Room"

Publishing Date	10/02/2022 at 1:00 P.M.
Estimated Cost	73350/-
Quotation Fee	200/- In favour of Principal, Miranda House University of Delhi.
Completion Time	30 Days
Quotation Submission Date	18/02/2022 at 4.00pm
Quotation Opening Time	19/02/2022 at 3.00pm

- Bids will be opened as per date/time on mentioned above.
- Bidder has down loaded the Quotation from the college website.
- The above Quotation should reach Miranda House College Office by hand on or before 18/02/2022 up to 4:00 p.m.
- The tender fee is non- Replaceable.
- The unit rate for any items should be Quotation inclusive of GST.
- For general rules and directive condition of Contract, the tender shall refer to "CPWD General Condition of Contract – 2014". Except for exception mentioned in this document, which will form a part of the Agreement will up to date correction slips.


Offg. Principal


19/2/2022

Estimate

Providing & Fixing APP sheet on roof of NCC room.

S.no	Items	Qty	Unit	RATE	Amount
1	Providing and fixing APP (Atactic Polypropylene Polymer) modified prefabricated five layer 2 mm thick water proofing membrane, black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufacture of density at 25°C .87 - 0.89 kg/ litre and viscosity 70 - 160 cps. Over the primer coat the layer of membrane shall be laid using Butane torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse irection at 23°C as 350/300 N/ 5 cm. Tear strength in longitudinal and transverse direction as 60/80N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorized applicator of the manufacture of membrane. 14.89.1 2mm (for corrugated roof sheets).	90	Sqm		
2	With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	90	Sqm		
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	180	Sqm		
4	Distemper with oil bound distemper two or more coats.	180	Sqm		
5	Repair of toilet water tap etc complete.	1	job		
6	Cleaning of sewer line NCC room to Ground.	30	mtr		
7	Painting with sythatic enamel paint two or more coats.	20	Sqm		
	Total				