

MIRANDA HOUSE
UNIVERSITY OF DELHI


Date: 21.03.2022

Notice Inviting Quotation

Sealed quotation an invited from the civil working contractors of the College/ CPWD/ Delhi University.
"Repair and Distemper work in Hostel Dining Hall patch area, Common room, and room no A-
302,303,305,306,313,D-205."

Publishing Date	21/03/2022 at 1:00 P.M.
Estimated Cost	92578/-
Quotation Fee	200/- In favour of Principal, Miranda House University of Delhi.
Completion Time	30 Days
Quotation Submission Date	01/04/2022 at 4.00pm
Quotation Opening Time	02/04/2022 at 3.00pm

- Bids will be opened as per date/time on mentioned above.
- Bidder should download Quotation from the college website.
- The above Quotation should reach Miranda House College Office by hand on or before 01/04/2022 up to 4:00 p.m.
- The tender fee is non- Refundable.
- The unit rate for any items should be Quotation inclusive of GST.
- For general rules and directive condition of Contract, the tender shall refer to "CPWD General Condition of Contract – 2014". Except for exception mentioned in this document, which will form a part of the Agreement will up to date correction slips.


Offg. Principal

ESTIMATE

Name of work: Repair and Distemper work in Hostel Dining hall patch area, Common room and room no A-302,303,305,306,313,D-205.

S.no	Items	Qty	Unit	Rate	Amount
1	13.2 15 mm cement plaster on the rough side of single or half brick wall of mix : 13.2.1 1:4 (1 cement: 4 fine sand).	70	sqm		
2	13.81 Distemping with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. 13.81.2 Two coats.	600	sqm		
3	13.91 Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	600	sqm		
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	70	sqm		
5	Dismantling of old termite infected furniture.	20	sqm		
6	Removal of malba at college campus.	12	Cum		
7	Finishing walls with textured exterior paint of required shade : 13.45.1 New work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/10 sqm	40	sqm		
				Total	