

MIRANDA HOUSE  
UNIVERSITY OF DELHI


Date: 24.03.2022


Notice Inviting Quotation

Sealed quotation an invited from the civil working contractors of the College/ CPWD/ Delhi University.  
"Repair of water proofing and distemper work in Teacher flats 8,32." (8 and 32)

Publishing Date	25/03/2022 at 1:00 P.M.
Estimated Cost	47359/-
Quotation Fee	200/- In favour of Principal, Miranda House University of Delhi.
Completion Time	25 Days
Quotation Submission Date	6/04/2022 at 4.00pm
Quotation Opening Time	7/04/2022 at 3.00pm

- Bids will be opened as per date/time on mentioned above.
- Bidder will down load the Quotation from the college website.
- The above Quotation should reach Miranda House College Office by hand on or before 06/04/2022 up to 4:00 p.m.
- The tender fee is non- Refundable.
- The unit rate for any items should be Quotation inclusive of GST.
- For general rules and directive condition of Contract, the tender shall refer to "CPWD General Condition of Contract – 2014". Except for exception mentioned in this document, which will form a part of the Agreement will up to date correction slips.

  
Offg. Principal



## ESTIMATE

Name of work: Repair of water proofing and Distemper work in Teaching Flat 8,32.					
S.no	Items	Qty	Unit	Rate	Amount
1	13.2 15 mm cement plaster on the rough side of single or half brick wall of mix : 13.2.1 1:4 (1 cement: 4 fine sand).	25	sqm		
2	13.81 Distemping with 1st quality acrylic distemper, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. 13.81.2 Two coats.	60	sqm		
3	13.91 Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	60	sqm		
4	Finishing walls with water proofing cement paint of required shade : 13.44.1 New work (Two or more coats applied @ 3.84 kg/10 sqm)	40	sqm		
5	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	25	sqm		
6	providing carpanter for carpantery work	3	days		
7	Providing and fixing ply wood.	2	sqm		
8	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	30	kg		
9	Repair of terrace water proofing work with raking out joints and re-filling the joints with Dr fixit chemical.	120	sqm		
				Total	