

MIRANDA HOUSE
UNIVERSITY OF DELHI



Date: 12.04.2022

Notice Inviting Quotation

Sealed quotation an invited from the civil working contractors of the College/ CPWD/ Delhi University.
"Providing water arrangement in Hostel Mess"

Publishing Date	12/04/2022 1:00 P.M.
Estimated Cost	49,657/-
Quotation Fee	200/-
Completion Time	30 Days
Quotation Submission Date	22/04/2022
Quotation Opening Time	23/04/2022

- Bids will be opened as per date/time on mentioned above.
- Bidder has down loaded the Quotation from the college website.
- The above Quotation should reach Miranda House College Office by hand on or before 22/04/2022 up to 4:00 p.m.
- The tender fee is non- Replaceable.
- The unit rate for any items should be Quotation inclusive of GST.
- For general rules and directive condition of Contract, the tender shall refer to "CPWD General Condition of Contract – 2014". Except for exception mentioned in this document, which will form a part of the Agreement will up to date correction slips.


Offg. Principal


MIRANDA HOUSE

UNIVERSITY OF DELHI

Quotation

Water arrangement in Hostel Mess

S.NO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : 17.10.1 . Kitchen sink without drain board 17.10.2.1 610x510 mm bowl depth 200 mm .	2	NOS		
2	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall.				
	18.7.1 15 mm nominal outer dia Pipes	3	MTR		
	18.7.2 20 mm nominal outer dia Pipes	6	MTR		
3	Providing and fixing brass stop cock of approved quality : 18.16.1 15 mm nominal bore .	2	NOS		
4	Providing and fixing uplasticised PVC connection pipe with brass unions : 18.21.1 30 cm length 18.21.2 45 cm length 18.21.2.1 15 mm nominal bore .	2	NOS		
5	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 18.51.1 15 mm nominal bore each 552.35	2	NOS		
6	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 18.53.1 15mm nominal bore .	2	NOS		

7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	45	KG		
8	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in 6.12.2 cement mortar 1:4 (1 cement : 4 coarse sand).	4	SQM		
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).	0.35	CUM		
10	Centering and shuttering including strutting, propping etc. and removal of form for : 5.9.1 5.9.3 Suspended floors, roofs, landings, balconies and access platform .	2	SQM		
11	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade 8.2.2.1 Area of slab upto 0.50 sqm .	2	SQM		

12	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. 10.25.2 In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works ,Providing and fixing Bison board 10mm thick both side the frame and painting etc comliete as per the direction of Engg-in-charge.		96 sqft		
				TOTAL	