

MIRANDA HOUSE
UNIVERSITY OF DELHI


Date: 26.04.2022

Notice Inviting Quotation

Sealed quotation an invited from the civil working contractors of the College/ CPWD/ Delhi University.
"Repair of RCC Heritage pigeon water pot area , RCC Balcony railing, Warden room, medical room in hostel"

Publishing Date	28/04/2022 1:00 P.M.
Estimated Cost	62,481/-
Quotation Fee	200/-
Completion Time	30 Days
Quotation Submission Date	09/05/2022
Quotation Opening Time	10/05/2022

- Bids will be opened as per date/time on mentioned above.
- Bidder has down loaded the Quotation from the college website.
- The above Quotation should reach Miranda House College Office by hand on or before 09/05/2022 up to 4:00 p.m.
- The tender fee is non- Replaceable.
- The unit rate for any items should be Quotation inclusive of GST.
- For general rules and directive condition of Contract, the tender shall refer to "CPWD General Condition of Contract – 2014". Except for exception mentioned in this document, which will form a part of the Agreement will up to date correction slips.


Offg. Principal

MIRANDA HOUSE

UNIVERSITY OF DELHI

ESTIMATE

Repair of RCC Heritage pigeon water pot area, RCC Balcony railing ,warden room,medical room in

S.NO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	15 mm cement plaster on the rough side of single or half brick wall of mix : 13.2.1 1:4 (1 cement: 4 fine sand) sqm 307.90	30	sqm		
2	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer sqm 153.45	200	sqm		
3	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : 13.61.1 Two or more coats on new work sqm 121.55	20	sqm		
4	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. sqm 18.25	200	sqm		
5	Dismantling old plaster or skirting raking out	30	sqm		
6	Hacking of concrete to remove the bottom	4	sqm		
7	Providing and placing in position micro-concrete as per the direction of Engineer-in-charge.	0.25	cum		
8	Providing and fixing water tight shuttering,centering including strutting,propping etc and removal of form for.	3	sqm		
9	Removal of malba at site,out side the campus.	1	job work		
				TOTAL	