

**MIRANDA HOUSE
UNIVERSITY OF DELHI**

Date: 16.09.2022

Notice Inviting Quotation

Sealed quotation an invited from the civil working contractors of the College/ CPWD/ Delhi University.
"Repair and distemper work in Teacher flat no-7"

Publishing Date	20.09.2022 1:00 P.M.
Estimated Cost	55694/-
Quotation Fee	200/- (Bank Draft In favour of Principal Miranda House.)
Completion Time	25 Days
Quotation Submission Date	28.09.2022
Quotation Opening Date	29.09.2022

- Bids will be opened as per date/time on mentioned above.
- Bidder has down loaded the Quotation from the college website.
- The above Quotation should reach Miranda House College Office by hand on or before 28.09.2022 up to 3:00 p.m.
- The tender fee is non- Replaceable.
- The unit rate for any items should be Quotation inclusive of GST.
- For general rules and directive condition of Contract, the tender shall refer to "CPWD General Condition of Contract – 2014". Except for exception mentioned in this document, which will form a part of the Agreement will up to date correction slips.

The above draft should reach Miranda House, University of Delhi, Delhi 110007 in person on or before 28.09.2022 upto 03.00PM.

B. d

Principal

16.9.2022

MIRANDA HOUSE					
UNIVERSITY OF DELHI					
Repair and distemper work in teacher flat no-7.					
S.NO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	10	Sqm		
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	600	Sqm		
3	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats)	600	Sqm		
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	50	Sqm		
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	90	Sqm		
6	12 mm Cement plaster 1:4	10	Sqm		
				Total	

PRINCIPAL