

MIRANDA HOUSE
UNIVERSITY OF DELHI

Date: 11.10.2022

Notice Inviting Quotation

Sealed quotation an invited from the civil working contractors of the College/ CPWD/ Delhi University.
"Repair of class room for BE-EL-ED"

Publishing Date	11.10.2022 1:00 P.M.
Estimated Cost	39980/-
Quotation Fee	200/- (Bank Draft In favour of Principal Miranda House.)
Completion Time	20 Days
Quotation Submission Date	21.10.2022
Quotation Opening Date	22.10.2022

- Bids will be opened as per date/time on mentioned above.
- Bidder has down loaded the Quotation from the college website.
- The above Quotation should reach Miranda House College Office by hand on or before 21.10.2022 up to 3:00 p.m.
- The tender fee is non- Replaceable.
- The unit rate for any items should be Quotation inclusive of GST.
- For general rules and directive condition of Contract, the tender shall refer to "CPWD General Condition of Contract – 2014". Except for exception mentioned in this document, which will form a part of the Agreement will up to date correction slips.

The above draft should reach Miranda House, University of Delhi, Delhi 110007 in person on or before 21.10.2022 upto 03.00PM.

for Nandini Bala
Principal

11/10/2022

MIRANDA HOUSE

UNIVERSITY OF DELHI

Repair of class room for BE-EL-ED.

S.NO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	30	Sqm		
2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. 14.1.1 With cement mortar 1:4 (1 cement : 4 fine sand)	30	Sqm		
3	Repair of old false ceiling Remove old tiles and replace with new Armstrong 600x600 ceiling tiles and replace the damage frames fitting etc complete check and repair the suspended G.I. slotted cleats member and dush fasteners, channels rawl plugs at every junction.	3	Sqm		
4	Providing and applying Dr Fixit chemical pidicrete URP 301 Coating on concrete surface as per the specification.	30	Sqm		
5	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer .	160	Sqm		
6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	60	Sqm		
				Total	