

MIRANDA HOUSE
UNIVERSITY OF DELHI

Date: 17.10.2022

Notice Inviting Quotation

Sealed quotation an invited from the civil working contractors of the College/ CPWD/ Delhi University.
"Repair of Chajjas at front of BLT ground floor and first floor"

Publishing Date	17.10.2022 1:00 P.M.
Estimated Cost	185242/-
Quotation Fee	200/- (Bank Draft In favour of Principal Miranda House.)
Completion Time	30 Days
Quotation Submission Date	28.10.2022
Quotation Opening Date	29.10.2022

- Bids will be opened as per date/time on mentioned above.
- Bidder has down loaded the Quotation from the college website.
- The above Quotation should reach Miranda House College Office by hand on or before 28.10.2022 up to 3:00 p.m.
- The tender fee is non- Replaceable.
- The unit rate for any items should be Quotation inclusive of GST.
- For general rules and directive condition of Contract, the tender shall refer to "CPWD General Condition of Contract – 2014". Except for exception mentioned in this document, which will form a part of the Agreement will up to date correction slips.

The above draft should reach Miranda House, University of Delhi, Delhi 110007 in person on or before 28.10.2022 upto 03.00PM.


Principal


MIRANDA HOUSE
UNIVERSITY OF DELHI

Repair of chajjas at front of BLT ground floor and first floor.

S.no	Items	Qty	Unit	Rate	Amount
1	12 mm cement plaster of mix : 13.1.1 1:4 (1 cement: 4 fine sand) .	100	Sqm		
2	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer .	200	Sqm		
3	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer[1]in-charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding.	200	Sqm		
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	200	Sqm		
5	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. sqm 39.00	100	Sqm		
6	Applying DR Fixit chemical URP-301 on concrete and ,plastered surface.	200	Sqm		
7	Removal of malba at site and college campus area.	10	Cum		
	Total				