

MIRANDA HOUSE
UNIVERSITY OF DELHI

Date: 09.12.2022

Notice Inviting Quotation

Sealed quotation an invited from the civil working contractors of the College/ CPWD/ Delhi University.
"Providing Pantery in Hostel office and water tap area in Hostel"

Publishing Date	09/12/2022 1:00 P.M.
Estimated Cost	1,60,081/-
Quotation Fee	500/- (In favour of Principal Miranda House)
Completion Time	30 Days
Quotation Submission Date	19/12/2022
Quotation Opening Time	20/12/2022

- Bids will be opened as per date/time on mentioned above.
- Bidder has down loaded the Quotation from the college website.
- The above Quotation should reach Miranda House College Office by hand on or before 19/12/2022 up to 4:00 p.m.
- The tender fee is non- Replaceable.
- The unit rate for any items should be Quotation inclusive of GST.
- For general rules and directive condition of Contract, the tender shall refer to "CPWD General Condition of Contract – 2014". Except for exception mentioned in this document, which will form a part of the Agreement will up to date correction slips.



Principal

MIRANDA HOUSE

UNIVERSITY OF DELHI

Quotation

Providing Pantery in Hostel office & water tap area

S.NO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer .	50	Sqm		
2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : 13.61.1 Two or more coats on new work .	10	Sqm		
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	70	Sqm		
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	25	Sqm		
5	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : 17.10.2 Kitchen sink without drain board 17.10.2.1 610x510 mm bowl depth 200 mm each 3631.55	5	Nos		

6	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 18.8.2 20 mm nominal outer dia Pipes .	35	Mtr		
7	Providing and fixing brass bib cock of approved quality : 18.15.2 20 mm nominal bore .	1	Nos		
8	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : 18.18.2 20 mm nominal bore .	2	Nos		
9	Providing and fixing uplasticised PVC connection pipe with brass unions : 18.21.1 30 cm length 20 mm nominal bore .	6	Nos		
10	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 18.53.1 15mm nominal bore .	2	Nos		
11	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	500	Litre		
12	15 mm cement plaster on the rough side of single or half brick wall of mix : 13.2.1 1:4 (1 cement: 4 fine sand) .	15	Sqm		

13	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).	1.6	Cum		
14	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform sqm 693.05	8	Sqm		
15	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	110	Kg		
16	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in : 6.12.2 cement mortar 1:4 (1 cement : 4 coarse sand) .	3.5	Sqm		
17	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	30	Sqm		

18	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. 8.2.1 Raj Nagar Plain white marble/ Udaipur green marble/ Zebra black marble Granite of any colour and shade 8.2.2.1 Area of slab upto 0.50 sqm .	10	Sqm		
				Total	