

MIRANDA HOUSE
UNIVERSITY OF DELHI

Date: 19.12.2022


Notice Inviting Quotation

Sealed quotation an invited from the civil working contractors of the College/ CPWD/ Delhi University.
"Providing and fixing Tectile tiles at gate no 1&2"

| | |
|---------------------------|----------------------|
| Publishing Date | 20/12/2022 1:00 P.M. |
| Estimated Cost | 170929/- |
| Quotation Fee | 200/- |
| Completion Time | 30 Days |
| Quotation Submission Date | 26/12/2022 |
| Quotation Opening Date | 26/12/2022 |

- Bids will be opened as per date/time on mentioned above.
- Bidder has down loaded the Quotation from the college website.
- The above Quotation should reach Miranda House College Office by hand on or before 26/12/2022 up to 4:00 p.m.
- The tender fee is non-refundable.
- The unit rate for any items should be Quotaed inclusive of GST.
- For general rules and directive condition of Contract, the tender shall refer to "CPWD General Condition of Contract – 2014". Except for exception mentioned in this document, which will form a part of the Agreement will up to date correction slips.


Principal



MIRANDA HOUSE

UNIVERSITY OF DELHI

Providing and Fixing Tactile tiles at gate no 1 & 2

| S.NO | ITEMS | QTY | UNIT | RATE | AMOUNT |
|------|--|------|------|-------|--------|
| 1 | Providing and laying tactile tile (for vision impaired persons as per standards) of size 300x300x9.8mm having with water absorption less than 0.5% and conforming to IS:15622 of approved make in all colours and shades in for outdoor floors such as footpath, court yard, multi modals location etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge. | 60 | SQM | | |
| 2 | Dismantling inter locking tiles and re-fixing placing in position as per site requirement | 60 | SQM | | |
| 3 | Removal of malba at site | 1 | Trip | | |
| 4 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 4.1.2 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size) cum 7210.55 4.1.3 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size) | 2.25 | CUM | | |
| | | | | | |
| | | | | | |
| | | | | Total | |